BANGALORE DIVISION.

The 20th July 1896.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, B. C. W. D. Range, Bangalore, up to 31st July 1896, for constructing a pure-water tank on Guttahalli rock, High Ground, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1896.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's office at Bangalore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a pure-water tank on Guttahalli rock" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yd.	344
Concrete with surki mortar	C. ft.	9,304
Brick in surki mortar	"	7,366
Plastering with Portland cement	Sqr.	142·21
Burnt stone slabs 9″ thick with edge dressed	S. ft.	527
Do 6″ do	"	8,150
Beams (quarried)	R. ft.	648
Burnt slabs 3″ thick, dressed	S. ft.	606
Galvanized iron wire netting in teak frames	"	352
Painting with chunam	Sqr.	76·07
Trap door (4′ × 6′)	No.	1
Teak shutters with frames for valve house	S. ft.	60
Iron staircase	No.	1

Steps.

Excavation, foundation	C. yd.	2
Stone in clay	C. ft.	51
Brick in chunam	"	83
Plastering with chunam	Sqr.	1·66
Slabs for steps (4″ thick dressed)	S. ft.	39
Clearing site, removing boulders and stepping rock, &c.	Lump sum	

H. D. RICE, *Sub-Asst. Engr., B. C. W. D. Range.*

MYSORE DIVISION.

The 3rd July 1896.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 31st July 1896, for improving the Rajaparameswari channel. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th April 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Rajaparameswari channel" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.*
Excavation including deepening and widening—		
Hard rock	C.yds.	1,597
Soft rock	Do	1,091
Stony soil	Do	986
Gravel	Do	6,859
Sand	Do	4,014
Clay	Do	13,485
Earthwork, bund raising	Do	3,519
Watering, tamping and forming bund only	Do	4,181
Silt dams new	No.	5
Do old repairing	Lump sum	
Raising the waste weir by 6″	Do	
Do the panaboo	Do	
Widening the panaboos	Do	
Index stones	Each	
Grade stones	Do	
Sluice stones	Do	
Mile stones	Do	

J. H. KARVE, *Executive Engineer.*

HASSAN DIVISION.

The 26th June 1896.

Tenders are hereby invited for constructing super-passages, &c., on improving and extending north channel of Sriramdevar dam.

2. The plans, estimates, and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor, and forwarded in sealed covers to the Executive Engineer before the 25th July 1896. The work should be completed by the end of June 1897.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 300 as earnest money.

6. Within eight days of the acceptance of the tender the contractor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities of items of work required is given below :—

10. These quantities are not guaranteed.

Items of work.	*Per.*	*Quantity.*
Constructing super-passage across Koglihalla and channel deviation—		
Earthwork excavation	C. yds.	11,944
Removing boulders	,,	100
Earthwork using to bund	,,	2,975
Rough stone work, new	,,	554
Jelly felling	,,	250
Clearing site and excavating foundation	Lump sum	
Rough stone in surki mortar	C. ft.	2,905
Burnt brick do	,,	5,565
Plastering do	Sqr.	3,000
Cut stone work	C. ft.	265
Burnt stone slabs	S. ft.	1,579
Surki concrete	C. ft.	919
Improving Tarahalli Vod—		
Earthwork excavation	C. yds.	563
Rough stone in surki mortar	C. ft.	6,765
Burnt brick do	,,	8,715
Plastering	Sqrs.	37·44
Cut stone work	C. ft.	686
Burnt stone slabs	S. ft.	5,875
Surki concrete	C. ft.	3,675
Distribution and scouring sluices—		
Excavation	C. yds.	36
Rough stone in surki mortar	C. ft.	707
Burnt brick in do	,,	566
Burnt stone slabs	S. ft.	586
Plastering	Sqrs.	7·00
Rough stone work, new	C. yds.	6
Teakwood shutters with iron strips, &c., tarring	C. ft.	52

A. S. NAGAVKAR, *Executive Engineer.*